

ADDENDUM NUMBER 2

SEDALIA, MO
COME GROW WITH US

Title: North Central Neighborhood Connect Sedalia Revitalization
Owner: City of Sedalia, Missouri
Engineer: Wilson & Company, Inc., Engineers & Architects

ISSUE DATE: **November 8, 2024.**

Bidders are hereby notified of the following changes, additions, modifications, information and clarification for the above project, for which Bids are to be received on Friday, **November 22, 2024**, at 2:00 PM are amended as follows:

QUESTIONS AND CLARIFICATIONS

1. Plans and bid documents do not need to be purchased to be considered a bidder.
2. Construction Staking will be the sole responsibility of the contractor.
3. The City will be performing all demolition work as shown in the plans. The Contractor will be required to coordinate with the City to schedule demolition ahead of starting any proposed work.

PLANS

1. No Changes

PROJECT MANUAL

1. Revised the Proposal to include the base bid form. To be considered a responsive bidder the bid alternates will still need to be filled out.

The base bid form page is attached.

2. Revised Special Provisions, page 69, SP-4 Measurement and Payment Bid Item No. 1 Mobilization to: "Payment shall be at the lump sum bid price. The payment shall include full compensation for the movement of all equipment and personnel required by the contractor to perform the work in accordance with the plans and specifications and to coordinate with the City to schedule any demolition work prior to starting the proposed work as set forth in the plans."

The updated page 69 is attached.

NOTE: Bidders must acknowledge receipt of this Addendum by listing the number and date, where provided, on the Proposal.

PROPOSAL

TO THE CITY OF SEDALIA, MISSOURI:

Pursuant to and in compliance with the Notice to Contractors and having examined the plans and specifications with related documents and the site(s) of the proposed work, the undersigned bidder proposes and agrees, if this proposal is accepted, to furnish all labor, materials, tools, supplies, equipment and supervision and to do all other work necessary for the **NORTH CENTRAL NEIGHBORHOOD CONNECT SEDALIA REVITALIZATION, Project 2025-007, dated October 22, 2024**, as noted in these contract documents for the following price(s):

Item No.	Description	UNIT	Estimated Quantity	Unit Cost	Amount
BASE BID					
1	Mobilization	LS	1		
2	Construction Staking	LS	1		
3	Temporary Traffic Control	LS	1		
4	Erosion Control	LS	1		
5	Remove and Reset Sign	EA	3		
6	Curb & Gutter (Type 1)	LF	75		
7	Curb & Gutter (Type 2)	LF	52		
8	Integral Sidewalk Curb	LF	20		
9	Concrete Sidewalk (4")	SF	114,711		
10	ADA Sidewalk Ramp	EA	143		
11	Truncated Domes (Alleyways)	EA	38		
12	Concrete Flume	EA	1		
13	Residential Driveway (6")	SF	24,467		
14	Commercial Driveway (8")	SF	6,905		
15	Concrete Collar	EA	1		
16	8" HDPE	LF	37		
17	12" HDPE	LF	411		
18	15" HDPE	LF	27		
19	18" HDPE	LF	9		
20	24" HDPE	LF	9		
21	Seeding	AC	2		

TOTAL AMOUNT OF BASE BID: \$ _____

BID ALTERNATES: Upon acceptance of the base bid, the Owner reserves the right to select one or more in the order of Alternates listed herein to be included in the total contract amount. The total contract amount shall be adjusted by deducting the specified amounts of the accepted alternates from the base bid. In order for a Bid to be responsive, the Bidder must submit each Alternate bid listed below. The failure to quote an amount will result in the bid being rejected as non-responsive.

SPECIAL PROVISIONS

These Special Provisions describe the work and set forth requirements and modifications to the Standard Technical Specifications that are unique to this project. Should the requirements of these Special Provisions conflict with the Standard Technical Specifications, the requirements of these Special Provisions shall apply.

SP-1 Missouri Standard Specifications for Highway Construction

All references to the Missouri Standard Specifications for Highway Construction shall be revised to the latest "2011 edition".

SP-2 Manual on Uniform Traffic Control Devices (MUTCD)

All references to the Manual on Uniform Traffic Control Devices (MUTCD) shall be revised to "Latest Edition and its most current revisions."

SP-3 Utility Relocation Coordination

All utility relocation coordination shall be the responsibility of the Contractor.

SP-4 Measurement and Payment

Payment for this project shall be as specified below. All work shown in the contract drawings, or specified herein, shall be included in the items named in the proposal.

All materials, labor, equipment and overhead costs required for completion of this project, in accordance with the plans and specifications, shall be included in the total construction costs, which is a summation of the extensions of the items in the Proposal.

All costs in connection with the work, including mobilization, bonds, insurance and taxes, supplies and appurtenances, all construction plant, and the performance of all labor to complete the work, shall be included in the items listed in the proposal. Should the Contractor find that the quantity of any item will exceed that which is shown in the Proposal, he must notify the Engineer immediately so that it may be determined if a change order will be required.

Bid Item No. 1

Mobilization

(Lump Sum)

Payment shall be at the lump sum bid price. The payment shall include full compensation for the movement of all equipment and personnel required by the contractor to perform the work in accordance with the plans and specifications and to coordinate with the City to schedule any demolition work prior to starting the proposed work as set forth in the plans.

Bid Item No. 2

Construction Staking

(Lump Sum)

Payment shall be at the lump sum bid price. The payment shall include furnishing all materials, labor, and equipment to perform all construction staking for the project in accordance with the plans, standard details, and specifications. The cost of construction staking, and all other incidental items necessary for complete repair and installation of all components of the project are included in this bid item. This provision shall supersede Any Section of the Standard Technical Specifications that states the City will perform any construction staking or surveying including, but not limited to, Sections S-7, S-28, S-29, S-30, and S-31 of the Standard Technical Specifications.